Construction material waste management

"The main causes of construction material waste are inaccurate estimates, unrecorded site changes, excessive ordering, poor storage and unmeasured losses. Three solutions are a manual material register, a spreadsheet-based tracking system and a digital inventory system. I recommend spreadsheet tracking with daily physical measurements because it is affordable, practical and improves accuracy. For a brick wall, calculate the wall volume and divide it by the volume of one brick includin" *Generated by LeapSpace*

Construction Material Waste and Brick Wall Quantity Estimation at a Glance

Key Findings Table

Topic	Key finding	Practical implication	Citations
Main causes of waste	Construction material waste is largely driven by weak planning and execution control, especially design changes, incomplete documents, poor site layout, rework, and labor mistakes [1] [2] [3] [4].	Waste control should start before procurement and continue through site execution [1] [2] [3] [4].	[1] [2] [3] [4]
Procurement-related waste	Excess procurement, inefficient ordering, and noncompliant purchases are recurring waste sources [1] [5] [6] [7].	Ordering should be linked to verified quantities and controlled updates [5] [6] [7].	[1] [5] [6] [7]
Storage and handling losses	Damage during transportation, poor handling, inadequate storage, and on-site damage repeatedly contribute to losses [7] [8] [9] [10].	Daily stock checks and protected storage are necessary, not optional [7] [8] [9] [10].	[7] [8] [9] [10]
Measurement and documentation	Waste estimation improves when actual design information and quantified elements are used instead of broad indexing or rough allowances [11] [12].	Measured quantities and documented losses should replace rough percentage assumptions where possible [11] [12].	[11] [12]

Topic	Key finding	Practical implication	Citations
Manual registers	Traditional manual measurement and paper-based recording remain simple and familiar, but manual workflows are labor-intensive, error-prone, and hard to verify [13] [14].	Suitable where digital capability is minimal, but weak for traceability [13] [14].	[13] [14]
Spreadsheet tracking	Spreadsheet-based tracking aligns with the broader evidence that structured measurement and documentation improve control while remaining practical in non-fully-digital settings [11] [12] [13] [14].	A spreadsheet reconciled daily against physical counts is a defensible low-cost control method [11] [12] [13] [14].	[11] [12] [13] [14]
Digital inventory systems	BIM, image-based, and sensor-supported systems can improve speed, traceability, and quantity accuracy, but evidence here is limited on affordability and adoption barriers for small-to-medium projects [14] [15] [16] [17] [18] [19].	Advanced systems are promising, but not yet the best-evidenced universal choice for typical site inventory control [17] [19].	[14] [15] [16] [17] [18] [19]
Brick wall quantity estimation	The supported method is to calculate wall volume, divide by the volume of one brick including mortar allowance, then add a waste factor if project practice requires it [20] [21] [22].	Accurate brick control requires both takeoff and separate loss accounting [20] [21] [22].	[20] [21] [22]

Direct Answer

Your recommendation is broadly supported by the evidence: for small- to medium-scale construction projects, **spreadsheet tracking with daily physical measurement** is a practical middle-ground solution because the literature consistently supports tighter measurement, quantified inputs, and better documentation, while the evidence for more advanced digital systems is stronger on technical capability than on field affordability or adoption feasibility [11] [12] [13] [14] [17] [19].

For the brick wall calculation, use:

Wall volume = length x height x thickness [20] [21] [22]
Number of bricks = wall volume / volume of one brick including mortar joint allowance [20] [21] [22]
Final required bricks = number of bricks + waste allowance (if required by project practice) [20] [21] [22]

The query is truncated, so an exact numeric answer cannot be completed because the wall dimensions, brick dimensions, mortar joint thickness, and waste allowance were not provided [20] [21] [22].

Confidence level: High - The recommendation is directly aligned with repeated evidence favoring better measurement and documentation, while the limitation on exact numeric calculation is explicit in the supplied query [11] [12] [13] [14].

Study Scope

This report covers research on:

- causes of construction material waste in building projects, especially estimation errors, site changes, procurement issues, storage, handling, and rework [1] [2] [3] [4] [5] [6] [7] [8] [9] [10]
- quantity takeoff and waste-estimation methods for masonry and related wall systems [15] [16] [18] [20] [21] [22]
- manual, spreadsheet-compatible, and digital approaches to material tracking and quantity workflows [13] [14] [17] [19]

Methods represented in the evidence include manual takeoff, BIM and visual-programming workflows, image-based estimation, material conversion and mass-balance approaches, and sensor/digital waste-analysis systems [13] [14] [15] [16] [17] [18] [19] [20] [21] [22].

Assumptions & Limitations

- The supplied evidence strongly supports the **principle** of spreadsheet-plus-measurement control, but it does **not** include a direct head-to-head field study comparing manual registers, spreadsheets, and digital systems on cost, feasibility, and accuracy in small-to-medium projects [13] [14] [17] [19].
- The brick-wall method is supported as a general procedure, but the query does not provide dimensions needed for a finished quantity calculation [20] [21] [22].
- Evidence on advanced digital systems is stronger for automation and traceability than for real-world adoption constraints in ordinary site settings [15] [16] [17] [19].

Suggested Further Research

- Conduct field comparisons of manual registers, spreadsheets, and lightweight digital tools on active sites [13] [14] [17] [19].
- Test whether **daily** physical measurement reduces waste more than weekly or periodic counts [11] [12].

Standardize masonry loss categories such as breakage, cutting waste, storage damage, and undocumented changes [4] [7] [20] [21].

Evaluate lifecycle cost and usability barriers for small-contractor adoption of digital tracking systems [17] [19].

Link brick quantity takeoff more explicitly to procurement variance and site-loss accounting workflows [20] [21] [22].

Full Report Body

Foundational Context

Construction material waste control has two distinct but connected tasks: **quantity takeoff** and **loss accounting** [11] [20] [21] [22]. Quantity takeoff estimates what should be built from design information, while loss accounting records the gap between what was planned, what was ordered, what was delivered, what was installed, and what was lost through damage, rework, over-ordering, or undocumented changes [4] [7] [11] [12] [22].

This distinction matters because waste is not caused by one issue alone. The evidence consistently shows interacting failures across estimating, documentation, procurement, storage, handling, and site execution [1] [2] [3] [4] [5] [6] [7] [10]. Taken together, these findings suggest that good quantity estimation without daily control is insufficient, and daily control without a reliable baseline quantity is also insufficient [11] [12] [20] [21] [22].

Confidence level: High - Multiple sources converge on the need to combine accurate quantities with separate waste/loss tracking [11] [12] [20] [21] [22].

Drivers of Construction Material Waste

Estimation Errors and Incomplete Design Information

The evidence supports the view that inaccurate estimates are a major upstream cause of material waste [4] [11] [12]. Waste estimation improves when teams use actual design information and quantified building elements rather than broad indexing or rough assumptions [11] [12]. In practical terms, when estimates are based on incomplete drawings, simplified assumptions, or insufficiently quantified elements, procurement becomes less precise and downstream material control weakens [4] [11] [12].

Incomplete design documents and design changes also contribute directly to waste because they disrupt material forecasting and increase the risk of mismatch between ordered and required quantities [1] [4]. This is not just a design problem; it becomes a site waste problem once wrong quantities have already been purchased or partially installed [1] [4].

Unrecorded Site Changes and Rework

Unrecorded site changes, poor site layout, and labor mistakes are repeatedly identified as waste drivers because they create rework and material mismatch [1] [2] [3] [4]. Rework consumes additional materials beyond the original estimate, while undocumented changes prevent the project team from reconciling planned and actual usage [1] [3] [4].

Operationally, this means that even a correct initial estimate can become unreliable if change control is weak [1] [2] [4]. Taken together, the findings imply that loss accounting should include a specific category for change-related waste rather than absorbing it into a generic waste percentage [4] [22].

Excess Ordering, Storage Losses, and Handling Damage

Ordering and procurement practices are also central to waste generation. Excess procurement, inefficient ordering, and purchases that do not comply with specifications are all reported contributors [1] [5] [6] [7]. These issues often compound estimation weaknesses: poor quantity forecasting encourages over-ordering, and over-ordering increases the risk of storage deterioration and unused surplus [5] [6] [7].

Material mishandling is another recurring theme. Transportation damage, wrong handling, inadequate storage, and on-site damage all generate avoidable losses [7] [8] [9] [10]. This supports the user's emphasis on poor storage and unmeasured losses as major causes [7] [8] [9] [10].

Synthesis: Waste as a Management-and-Execution Problem

Across the evidence, material waste is best understood as a **management-and-execution problem** rather than a single estimating error [1] [2] [3] [4] [5] [6] [7] [10]. Estimation errors, undocumented changes, over-ordering, poor storage, and unmeasured losses are not isolated categories; they reinforce each other through weak control systems [4] [7] [10].

Confidence level: High - The evidence is consistent across multiple waste-cause studies [1] [2] [3] [4] [5] [6] [7] [10].

Material Control Approaches

Manual Material Registers and Paper-Based Stock Control

Manual registers and paper logs remain understandable and easy to introduce where site digital capability is limited, but the retrieved evidence shows that traditional manual measurement and recording are time-consuming, error-prone, and difficult to verify [13] [14]. These weaknesses matter because a stock-control method is only useful if it can be reconciled against procurement and installation records [13] [14].

A manual register can still provide a minimum control framework by listing planned quantities, deliveries, issues to work fronts, and closing balance, but its dependence on consistent human recording makes it vulnerable to omission and delayed updates [13] [14].

Spreadsheet-Based Tracking with Daily Physical Measurements

The strongest support for your recommendation comes indirectly but clearly from the evidence on measurement quality and structured documentation [11] [12] [13] [14]. Studies show that better quantified inputs improve waste estimation [11] [12], and that traditional fully manual workflows suffer from verification and efficiency problems that more structured digital workflows can reduce [13] [14].

A spreadsheet-based system sits between these two extremes. It is not directly benchmarked in the supplied studies against manual logs or advanced digital systems, but it matches the evidence-backed need for:

- a quantified baseline [11] [12]
- regular reconciliation between planned and actual quantities [20] [21] [22]
- a record structure that is easier to update and audit than paper-only systems [13] [14]

Taken together, these findings suggest that a spreadsheet with daily physical measurement is a pragmatic low-cost workflow for small- and medium-scale projects [11] [12] [13] [14]. A practical structure would track at least: planned quantity, ordered quantity, delivered quantity, installed quantity, damaged quantity, returned quantity, and unexplained variance [4] [7] [22]. This last element is an inference from the broader evidence on loss accounting rather than a directly tested spreadsheet template.

Inferred: Low confidence - A daily spreadsheet reconciliation model is not directly trialed in the retrieved studies, but it is a logical synthesis of the documented benefits of structured quantification and auditable workflows [11] [12] [13] [14] [22].

Digital Inventory Systems and Adoption Constraints

Digital systems, especially BIM, visual-programming workflows, image-based takeoff, and sensor-supported systems, show clear potential for improved speed, traceability, and quantity accuracy [14] [15] [16] [17] [18] [19]. Traditional manual takeoff is described as slow and error-prone, while BIM-enabled workflows can reduce processing time substantially and maintain high accuracy [13] [14]. Automated BIM methods can also achieve very small quantity deviations for wall-related elements, although model quality and missing wall models remain important constraints [16] [18].

Image-based methods can automate brick wall quantity estimation from photos, with accuracy improving when photos are taken close-up and when more than one brick is used as a reference [15]. Sensor-based and digital systems are also being used in waste sorting and analysis [17] [19].

However, the practical evidence is incomplete. The retrieved papers do not provide strong evidence on cost feasibility, adoption barriers, or routine inventory-tracking performance for small- to medium-scale projects [17] [19]. This creates a real decision tension: technically, digital systems may be superior; practically, they are not yet the best-evidenced default for ordinary site inventory control [14] [17] [19].

Confidence level: Medium-High - The technical benefits are well supported, but affordability and field adoption questions remain under-evidenced in the supplied material [14] [15] [16] [17] [18] [19].

Decision Comparison: Manual vs Spreadsheet vs Digital

System	Strengths	Weaknesses	Best-supported use case	Evidence strength
Manual register	Simple, familiar, low technical barrier [13] [14]	Labor-intensive, error-prone, weak traceability, hard verification [13] [14]	Minimal-control environments with very limited digital capacity [13] [14]	Medium [13] [14]
Spreadsheet tracking	Low-cost, structured, auditable, compatible with frequent measurement [11] [12] [13] [14]	Evidence gap on direct field comparisons; still depends on disciplined data entry [13] [14] [17] [19]	Small- to medium-scale projects needing practical control without high-tech investment [11] [12] [13] [14]	Medium [11] [12] [13] [14]
Digital inventory system	High traceability, speed, automation potential, strong quantity workflows [14] [15] [16] [17] [18] [19]	Limited evidence here on cost, adoption, and feasibility for typical smaller sites [17] [19]	Higher-capability environments with BIM/image/sensor infrastructure [14] [15] [16] [18]	Medium [14] [15] [16] [17] [18] [19]

The overall balance of evidence supports your recommendation as a **pragmatic** rather than **technically maximal** choice [11] [12] [13] [14] [17] [19].

Brick Wall Quantity Calculation Method

Core Procedure

The supported brick wall estimation method is:

1. **Calculate wall volume** = length x height x thickness [20] [21] [22].
2. **Calculate the volume of one brick including mortar allowance** [20] [21] [22].
3. **Divide wall volume by brick-with-mortar volume** to estimate the number of bricks [20] [21] [22].
4. **Add a waste allowance if required** by the project's estimating practice [20] [21] [22].

This approach is consistent with the broader literature that combines quantity takeoff with material conversion ratios, wastage levels, and mass-balance logic [20] [21] [22].

Why Mortar Allowance Matters

The query specifically notes “including” mortar, and that is important because the estimate should reflect the effective modular volume occupied by each brick in the wall rather than the brick unit alone [20] [21] [22]. Without this allowance, the number of bricks may be overstated relative to the built wall volume [20] [21] [22].

Why a Waste Factor Should Be Separate

The evidence suggests a methodological distinction between **required installed quantity** and **losses** [11] [12] [20] [21] [22]. Therefore, the cleanest workflow is:

> first compute the base brick quantity from wall geometry [20] [21] [22]
> then apply a separate waste allowance for breakage, cutting, handling, storage damage, or undocumented change [4] [7] [22]

This is preferable to embedding vague loss assumptions inside the base quantity calculation [11] [12] [22].

Limits on Exact Calculation

An exact brick count cannot be finalized from the supplied query because the wall dimensions, brick dimensions, joint thickness, and waste percentage are missing [20] [21] [22]. If those values are added, the above method can be completed directly [20] [21] [22].

Confidence level: High - The general method is directly supported; only the missing numeric inputs prevent a final arithmetic answer [20] [21] [22].

Practical Implementation Guidance

Based on the evidence, a practical site workflow for masonry material control would be:

- **Set the baseline quantity from measured wall geometry** rather than rough allowance methods [11] [12] [20] [21] [22].
- **Track deliveries and issues in a spreadsheet** so planned, delivered, installed, and damaged quantities can be reconciled [11] [12] [13] [14].
- **Take daily physical measurements or counts** to identify variance early, especially after design changes or major work progress [4] [11] [12].
- **Separate waste causes** into procurement variance, breakage/storage damage, cutting waste, and undocumented scope changes for clearer management action [4] [7] [22].
- **Escalate to digital tools selectively** where model quality, site capability, and project scale justify the added complexity [14] [16] [17] [18] [19].

The recommendation for spreadsheets is therefore strongest where affordability, ease of rollout, and routine discipline matter more than full automation [11] [12] [13] [14].

Conclusion

The evidence supports the user's framing of the main causes of construction material waste: inaccurate estimates, unrecorded site changes, excessive ordering, poor storage, and unmeasured losses are all consistent with the literature on planning, procurement, handling, and execution failures [1] [2] [3] [4] [5] [6] [7] [8] [9] [10].

Among the three proposed control approaches, **spreadsheet-based tracking with daily physical measurement** is the most defensible practical recommendation for small- to medium-scale projects in this evidence set because it aligns with the demonstrated value of better quantification and documentation while avoiding the unresolved affordability and adoption questions around more advanced digital systems [11] [12] [13] [14] [17] [19].

For brick walls, the correct method is to calculate the wall volume, divide by the volume of one brick including mortar allowance, and then add a separate waste allowance if needed [20] [21] [22]. A final numeric result requires the missing dimensions from the truncated query [20] [21] [22].

Overall confidence level: High - The waste-cause analysis and general brick-estimation method are strongly supported, while the spreadsheet recommendation is well-supported as a pragmatic synthesis rather than a direct comparative trial result [4] [7] [11] [12] [13] [14] [17] [19].

References

Sweis, G.J., Hiari, A., Thneibat, M., (...), Sweis, R.J. (2021) Understanding the causes of material wastage in the construction industry. *Jordan Journal of Civil Engineering*. https://www.scopus.com/pages/publications/85108652020

Imawan, R., Nayono, S.E. (2023) Construction waste management in the educational building project: A case study in the construction of teaching industry learning center building, Universitas Gadjah Mada. *AIP Conference Proceedings*. https://doi.org/10.1063/5.0128860

Purwanto, H., Ramadinayanti, S., Hasan, M.F.R. (2023) Waste material analysis for BoQ control on structural work using Building Information Modeling (BIM). *AIP Conference Proceedings*. https://doi.org/10.1063/5.0115065

Hashemi, M.H., Mohammad Hassani Mamaghani, N.H., Daie, M. (2014) Design and utilization wastes in construction. *ARPN Journal of Engineering and Applied Sciences*. https://www.scopus.com/pages/publications/84911958135

Roy, R.V., Beulah, M. (2025) Construction Waste: Key Causes and Reduction Approaches. *Lecture Notes in Civil Engineering*. https://doi.org/10.1007/978-981-95-1495-3_5

Soharu, A., NAVEEN, B.P., Sil, A. (2022) Construction waste - causes and solution: action research. *Proceedings of Institution of Civil Engineers: Waste and Resource Management*. https://doi.org/10.1680/jwarm.21.00045

Marinelli, M., Dolan, M., Spillane, J., Konanahalli, A. (2014) Material waste in the northern ireland construction industry: On-site management causes and methods of prevention. *Proceedings 30th Annual Association of Researchers in Construction Management Conference, ARCOM 2014*. https://www.scopus.com/pages/publications/84911434652

Arumugam, N., Nagapan, S., Kaliannan, S., (...), Arumugam, S. (2023) Causes of Mishandling Materials in Construction Sites. *AIP Conference Proceedings*. https://doi.org/10.1063/5.0141190

Nadarason, K., Nagapan, S., Arumugam, N. (2023) Preliminary survey on the root causes of mishandling materials occurrence at construction sites in central region Malaysia. *IOP Conference Series: Earth and Environmental Science*. https://doi.org/10.1088/1755-1315/1238/1/012031

Ghoneim, M.M., Halabya, A., Moussa, O.M., Hassan, A.A. (2025) An empirical assessment of material waste drivers and sustainability strategies in Egypt's construction sector. *Discover Sustainability*. https://doi.org/10.1007/s43621-025-01976-2

Hung, F.C., Kamaludin, N.S. (2017) Professionals' views on material wastage level and causes of construction waste generation in Malaysia. *Malaysian Construction Research Journal*. https://www.scopus.com/pages/publications/85018316937

Lam, P.T.I., Yu, A.T.W., Wu, Z., Poona, C.S. (2019) Methodology for upstream estimation of construction waste for new building projects. *Journal of Cleaner Production*. https://doi.org/10.1016/j.jclepro.2019.04.183

Saenpaeng, W., Tantrairatn, S., Chaphirom, A. (2025) Development of an Automated Workflow for Reinforced Concrete Structural Quantity Takeoff and Cost Estimation Using Visual Programming in a BIM Environment. *Engineering and Technology Horizons*. https://doi.org/10.55003/ETH.420402

Shick Alshabab, M., Vysotskiy, A., Petritchenko, M., Khalil, T. (2020) BIM-Based Quantity Takeoff in Autodesk Revit and Navisworks Manage. *Lecture Notes in Civil Engineering*. https://doi.org/10.1007/978-3-030-42351-3_36

Basri Başağa, H.B., Hacıefendioğlu, K. (2024) An Approach for Brick Wall Quantity Take-Off by U-Net Method Based on Deep Learning. *Turkish Journal of Civil Engineering*. https://doi.org/10.18400/tjce.1214798

Khosakitchalert, C., Yabuki, N., Fukuda, T. (2020) Development of bim-based quantity takeoff for light-gauge steel wall framing systems. *Journal of Information Technology in Construction*. https://doi.org/10.36680/j.itcon.2020.030

Sampaio, C.H., Ambrós, W.M., Cazacliu, B.G., (...), Liendo, M.A. (2021) Construction and demolition waste recycling through conventional jig, air jig, and sensor-based sorting: A comparison. *Minerals*. https://doi.org/10.3390/min11080904

Monteiro, A., Poças Martins, J. (2013) A survey on modeling guidelines for quantity takeoff-oriented BIM-based design. *Automation in Construction*. https://doi.org/10.1016/j.autcon.2013.05.005

Heck, H.H., Reinhart, D.R., Townsend, T., (...), Chakrabarti, S. (2002) A photogrammetric methodology for estimating construction and demolition waste composition. *Conference Proceedings - Joint 2002 CSCE/ASCE International Conference on Environmental Engineering - An International Perspective on Environmental Engineering*. https://www.scopus.com/pages/publications/23844550974

Li, Y., Zhang, X. (2013) Web-based construction waste estimation system for building construction projects. *Automation in Construction*. https://doi.org/10.1016/j.autcon.2013.05.002

Touran, A., Christoforou, C., Dantata, N., Wang, J. (2004) An estimating system for construction and demolition waste management. *Journal of Solid Waste Technology and Management*. https://www.scopus.com/pages/publications/4444330829

Kim, Y.-C., Hong, W.-H., Park, J.-W., Cha, G.-W. (2017) An estimation framework for building information modeling (BIM)-based demolition waste by type. *Waste Management and Research*. https://doi.org/10.1177/0734242X17736381